



राष्ट्रीय प्रौद्योगिकी संस्थान मणिपुर
NATIONAL INSTITUTE OF TECHNOLOGY MANIPUR

Imphal, Manipur, Ph. (0385) 2058566 / 2445812

E-mail:- director@nitmanipur.ac.in , Website : www.nitmanipur.ac.in

An Autonomous Institute under MHRD, Govt. of India.

No. NITM.1/(29-Estt)/Pur/Comp/Server/2016-904

Date: 11.11.2016

To,

.....
.....
.....

Subject: Enquiry for supply and installation of Copper power cable and raw power circuit balance distribution at Administration & Server Building, NIT Manipur.

Sir,

Please provide sealed rate quotation for supply of the following items:

Sl.	Item Description	Make	Qty.
MATERIALS			
1.	3.5 Core Copper cable, 25 sqmm, True armored, Original with company/ authorized supplier declaration	Havels/Gloster/ Polycab	120 Mtrs.
2.	3.5 Core Copper cable, 25 sqmm, True armored, Original with company/ authorized supplier declaration	Havels/Gloster/ Polycab	40 Mtrs.
3.	Suitable Lugs & Gland for 25 sqmm Cable, Pure Copper, Quality Certificate by OEM/ authorized supplier	Dowels/Jonson/ Cablegrip	12 Set.
4.	3.5 Core Copper cable, 70 sqmm, True armored, Original with company/ authorized supplier declaration	Havels/Gloster/ Polycab	90 Mtrs
5.	3.5 Core Copper cable, 70 sqmm, True armored, Original with company/ authorized supplier declaration	Havels/Gloster/ Polycab	40 Mtrs
6.	Suitable Lugs & Gland for 70 sqmm Cable, Pure Copper, Quality Certificate by OEM/authorized supplier	Dowels/Jonson/ Cablegrip	10 Set.
7.	3 Core Copper cable, 10 sqmm, True armored, Original with company/ authorized supplier declaration	Havels/Gloster/ Polycab	200 Mtrs.
8.	Suitable Lugs & Gland for 10 sqmm Cable, Pure Copper, Quality Certificate by OEM/ authorized supplier	Dowels/Jonson/ Cablegrip	20 Set.
9.	Perforated Cable Tray, 100mm width x 35mm depth cable tray with base	Standard	120 Mtrs.
10.	TPN, MCB type Lighting Distribution, Board (CPDB), flush mounted on wall, sheet, metal fabricated, powder coated, having, dust-proof and vermin proof, and hinged door, with all internals such as DIN rails, neutral-link, interconnected wiring complete with earthing lugs, housing following switchgears, 1 no., 63A, TPN MCB incomer + 24 nos, 6/10A, SP, MCB outgoing	Legrand/Sneider	2 Nos.
SERVICES			
1	Complete Installation & cable laying through underground, min. 2 fts digging, refilling, 2 layers (top + bottom) brick	Standard Practice	80 Mtrs.

	filling (horizontal shape) & sand filling, 100mm dia hume pipe at road crossing & drain crossing, 8 Nos. route marker with "LT cables" marking		
2	Complete Installation & cable laying through wall tray, clamping (1 Nos. in every 18 inch) by aluminium clamp with double screw method	Standard Practice	1 Lot.
3	Project Management, Documentation, Materials Delivery, Terminations & Connectorisations, Testing	Standard Practice	1 Lot.
Annual Maintenance Contract (AMC)			
1	Comprehensive work of AMC for maintenance of Copper power cable and raw power circuit balance distribution to be installed at Administration & Server Building, NIT Manipur		1 year

Yours sincerely,


 (R.K. Lalit Singh)
 Registrar NIT, Manipur

Terms & conditions:

1. Quotation should reach Registrar, NIT Manipur, Langol on 18.11.2016 at 4:00 P.M.
2. Quotation should be super scribed as “**Quotation for supply and installation of Copper power cable and raw power circuit balance distribution at Administration & Server Building, NIT Manipur**”
2. Prices must be inclusive of taxes.
3. Prices must be F.O.R NIT Manipur Stores, Langol, Imphal.

Copy to:

1. Member, Purchase Committee
2. Technical Officer, NIT Manipur for uploading in the website
3. CF/GF